



KETCHIKAN GATEWAY BOROUGH

1900 First Ave., Suite 210 • KETCHIKAN, ALASKA 99901

• 907/228-6625 • fax 907/228-6684

OFFICE OF THE BOROUGH MANAGER

July 29, 2010

KETCHIKAN GATEWAY BOROUGH

INSTALLATION OF A REPLACEMENT DOCK, LORING ALASKA

ADDENDUM NO. 4

This addendum forms a part of and modifies the bidding/contract documents as noted below. Respondents must acknowledge receipt of this addendum in the space provided on the proposal documentation form. Failure to do so will be considered an irregularity in the proposal and grounds for rejection.

SCOPE OF WORK paragraph changed as shown below:

Schedule for performance of the work which highlights durations of each stage of the work, and availability of contractor's personnel and equipment:

Stage 3 – Pick-up owner's floats **between November 23, 2010 9th and January 10, 2011 November 16th, 2010** or other specified date at a local barge company in Ketchikan. These dates will require coordination with the float construction contractor.

SCOPE OF WORK -- Add the following:

The existing floats that would be removed and replaced as part of the installation project will remain the property of the Loring Service Area and will be stored on site at a location determined by the Loring Service Area. The existing piles removed as part of the installation project will remain the property of the Loring Service Area and will be placed upland at Loring at a location determined by the Loring Service Area.

Specifications -- Section 05120 – Structural Steel

Change 2.1 Materials and Construction subsection 2.1 A 6 "Pipe sections with 12" O.D. or less shall be ASTM A53 Grade B, type E or S." to **"Pipe piles sections 12" or greater shall be ASTM A252 Grade 2 or better.**

KETCHIKAN GATEWAY BOROUGH

A handwritten signature in blue ink, appearing to read "Dan Bockhorst", is written over a horizontal line.

Dan Bockhorst, Borough Manager